

To be presented at the Geothermal Resources
Council Annual Meeting, Salt Lake City,
Utah, September 9-11, 1980

LBL-11107

CONF-800926--26


RECEIVED BY TIC SEP 2 1980

TEST RESULTS FROM THE 500 kW
DIRECT CONTACT PILOT PLANT AT EAST MESA

MASTER

Kenneth E. Nichols, Robert G. Olander and James L. Lobach

June 1980



DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

LEGAL NOTICE

This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

Presented at the 1980 Annual Meeting
of the Geothermal Resources Council
Salt Lake City, Utah, September 9-11, 1980

LBL-11107

MASTER

TEST RESULTS FROM THE 500 kW
DIRECT CONTACT PILOT PLANT AT EAST MESA

Kenneth E. Nichols, Robert G. Olander and James L. Lobach
Barber-Nichols Engineering Company
Arvada, Colorado 80002

September 1980

Prepared for the U.S. Department of Energy
under Contract W-7405-ENG-48
PO# 4158102

DISCLAIMER

This book was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

REA

TEST RESULTS FROM THE 500 kW
DIRECT CONTACT PILOT PLANT AT EAST MESA

Kenneth E. Nichols, Robert G. Olander
and James L. Lobach

Barber-Nichols Engineering Company
Arvada, Colorado 80002

ABSTRACT

A 500 kW power plant utilizing direct contact heat exchange (DCHX) between the geothermal brine and the isobutane (IC₄) working fluid is being operated at the East Mesa test facility. The power plant incorporates a 40-inch-diameter direct-contacter approximately 35 feet tall. The purpose of the pilot plant is to determine the feasibility of large-scale direct-contact heat exchange and power plant operation with the DCHX. The binary cycle offers higher conversion factors (heat energy transformed to electrical energy) than the flashed steam approach for geothermal brines in the 300°F to 400°F range and preliminary results indicate the DCHX system may have higher performance than the conventional tube-and-shell binary approach. This performance advantage results from the absence of any fouling and the very close pinch temperatures achieved in the DCHX itself.

The baseline performance tests for the plant were completed in January, 1980. The results of these tests and follow-on testing are covered in this summary. A complete description of the plant is presented in References 1 and 2.

INTRODUCTION

The pilot plant is to be used to establish design criteria for large direct contactors and evaluate the overall performance levels of direct contact binary power systems. The pilot plant includes all of the significant functions felt to be necessary in a complete direct contact binary power plant. The system includes a downhole pump to provide unflashed brine to the plant, a brine conditioning module used to eliminate excess undissolved gases that may be in the brine, a direct-contact heat exchanger, a power turbine and generator, condensers and reservoir for the working fluid and a recovery system to control the working-fluid losses in the effluent brine.

Testing began with the downhole REDA pump and continued through the brine delivery system including the sand trap and brine pump. The DCHX and hydrocarbon loop was then operated with vapor flow bypassing the power turbine module. During this period the instrumentation and control loops were set up and checked out and operator training was initiated. Safety systems such as the hydrocarbon gas detectors, fire system and vent systems were completely checked during this phase of testing.

Preliminary performance data were obtained for the hydrocarbon and brine pumps, DCHX, and condensers. The head and flow rates produced by the pumps were proper to support operation of the power plant. The brine temperature delivered to the plant by well 8-1 was 326°F, which is 14° below the design value of 340°F. At this lower brine temperature the DCHX met or exceeded performance specifications. At design brine flow rates (225 gpm), pinch temperature differences between the brine and isobutane were in the range of 1 or 2°F. This result indicates that high-performance direct-contact spray columns in this size range can be accomplished. The evaporative condensers showed no problem in providing design heat-transfer rates at reasonable temperature differences between ambient wet bulb and condensing isobutane.

PLANT PROCESS AND PERFORMANCE

The process flow diagram and selected cycle state points are shown in Figure 1. The plant brings the 340°F incoming brine through a sand and CO₂ separating vessel. The brine boost pump then increases the pressure of the brine to 453 psia for injection into a spray column configuration DCHX. The brine is cooled to 145°F and, after passing through a working-fluid recovery system, is returned to a facility pond for re-injection. The isobutane working fluid is pumped from the hotwell to a pressure of 485 psia for injection at the bottom of the DCHX. As the IC₄ flows to the top of the DCHX through the descending brine, the IC₄ is heated to a temperature of 250°F, boiled, superheated to a temperature of 255°F, and taken off the top of the heat exchanger as a vapor. The IC₄ vapor, along with small amounts of water vapor, passes through a single-stage radial-inflow turbine and to the condenser where the mixture is condensed at a temperature of 94°F and then returned to the hotwell. The hotwell separates the water and IC₄ liquid phases. The water fraction is directed to the recovery system and the IC₄ returns to the feed pump, completing the cycle.

A study of thermodynamic cycles for this direct contact geothermal pilot plant was made during the design definition of this pilot plant (Ref. 2). The fluids examined were isobutane, isopentane, and N-pentane. Isobutane showed the highest utilization factor at brine temperatures of 340°F.

The 500 kW pilot plant was designed to produce a net output of 500 kW with a brine

inlet temperature of 340°F at an ambient wet-bulb temperature of 64°F. Total plant parasitic losses were calculated to be 306.9 kW, resulting in a gross plant output of 806.9 kW. Design brine flow rate is 222 gpm, resulting in a predicted net plant output of 5.1 watt-hr/lb of brine. The power levels developed for the plant and its components are:

Component	Efficiency	kW
Condensers		77.7
IC ₄ organic pump	$\eta_p = 75\%$ $\eta_m = 90\%$	96.7
Brine pump	$\eta_p = 76\%$ $\eta_m = 90\%$	54.4
Discharge pump	$\eta_p = 70\%$ $\eta_m = 85\%$	2.1
Recovery system		15.0
	Subtotal	245.9
Gearbox	$\eta_{gb} = 97\%$	
Alternator	$\eta_{alt} = 95\%$	61.0
	Subtotal	306.9
Power turbine	$\eta = 83\%$	776.7
Hydraulic turbine	$\eta = 81\%$	30.2
	Total output	806.9
	Net output	500.0 kW

Three major factors influencing plant performance and cost are 1) the control of non-condensibles that contaminate the power cycle condenser, 2) the equipment required to limit working-fluid losses, and 3) the control of scaling or performance robbing deposits in critical components. These factors are not unrelated and control of one often impacts control of the other two. The 500 kW pilot plant has been designed to investigate and demonstrate viable solutions to all three factors.

MAJOR COMPONENT DESCRIPTION

The DCHX configuration is one of a spray tower, with the hot (335°F) brine injected at the top of the vessel and allowed to flow to the bottom, forming a continuous column of liquid approximately 30 feet high. Cold isobutane (94°F) is injected near the bottom of the vessel through a perforated plate, forming small "bubbles" of dispersed liquid. The isobutane is less dense and only sparingly soluble in the surrounding brine, and these droplets rise through the column absorbing heat through direct contact. Preheating, boiling, and superheating of the isobutane all take place in the same vessel.

If the downward velocity of the brine exceeds the rising droplet velocity, the IC₄ is swept out the bottom of the DCHX with the exiting brine. This carryunder condition is avoided through judicious selection of the vessel diameter. Based on available correlations of holdup (defined as the column fraction occupied by IC₄) and carryunder, an inside column diameter of 40 inches was selected. This diameter is expected to yield an actual holdup equal to 90% of the holdup that occurs just prior to carryunder conditions.

The IC₄ power turbine configuration is a radial inflow design operating at 25,000 rpm.

The impeller is 7.75 inches in diameter and the predicted efficiency is 0.83 at the design conditions. The turbine is provided with variable area nozzles. At a constant inlet pressure, flow rates of 60% to 120% of design can be accommodated with small changes in turbine efficiency. The turbine wheel is mounted directly on the high speed shaft of the gearbox, thereby eliminating any additional bearings and couplings.

The vapor mixture (IC₄, steam, and CO₂) leaving the DCHX, and thence the turbine, is returned to liquid by means of an evaporative condenser. An evaporative condenser is similar to a cooling tower with the cooling tower core replaced by the condensing coil. Working fluid vapor is condensed to liquid inside the condensing coil, the outside of which is continually wetted by a recirculating water system. Air is simultaneously blown upward over the coil causing a small portion of the recirculated water to evaporate. This evaporation removes heat from the coil, thereby cooling and condensing the working fluid vapor inside the coil. The evaporative condenser has lower parasitic power requirements and lower capital costs than the cooling tower approach.

The IC₄ recovery system is designed to remove 95% of the dissolved isobutane from the brine stream exiting the DCHX and return it to the hotwell. A two-stage flash operation is employed to separate the IC₄ from the brine stream. The flashed vapors are compressed and then cooled to recondense the IC₄.

TEST RESULTS

An electric submersible downhole pump was used to supply brine to the 500 kW plant. The pump was installed and started November 17, 1979. Except for a few intermittent power outages, the pump operated continuously for 5 months and 20 days. The pump then failed for causes not determined at the time of this writing. The downhole temperature is estimated to be approximately 350°F.

Based on measured flow rates, inlet and outlet conditions and column temperatures, the DCHX performed better than expected. Overall heat balances between brine cooling and IC₄ heating were very good, being within 2-3% in most cases. The most significant aspect of the data is the indicated low pinch temperature achieved over the entire operating flow rates. While the expected pinch temperature at plant design was estimated to be 7°F, the pinch temperature calculated at the actual conditions ranged from 1.1°F at high brine flow rates (Figure 2) to 3.7°F at low brine flow rates. No attempt was made during the first tests to flood the column to determine its operating limits. The close pinch temperatures achieved indicate that very little back mixing exists and that the flow is very stable in the 40 inch diameter column.

The close approach temperature demonstrated by this DCHX design offers the potential for high utilization factors for the DCHX binary system. Since fouling cannot occur in the DCHX, this high performance potential should exist for extended

periods. Continuing testing will establish the limits for this DCHX design.

A more detailed discussion of this entire test program is contained in the final report, Reference 3.

The turbine-generator was initially started January 15, 1980, for a total run time of 13.5 hours. During the preliminary plant runs, the generator output power was not measured directly due to instrumentation problems. A coarse measurement of output was made by monitoring generator amperage. These values appeared reasonable during the first startup.

ACKNOWLEDGEMENTS

The program is sponsored by the Department of Energy and the work is being performed under Contract W-7405-ENG-48 to the Lawrence Berkeley Laboratory.

The evaporative condenser performance was evaluated based on the heat transfer and the measured condensing temperature. The heat transfer performance is a function of hardware design and also the non-condensibles existing in the vapor stream. Figure 3 shows the condenser performance plotted as the ΔT between condensing wet bulb temperature versus heat load. The wet and bulb temperatures ranged from 48° to 54°F during these tests. The data indicates that the condensers were able to dissipate their heat at lower condensing temperatures than expected, thus exceeding their design performance.


REFERENCES

1. Barber-Nichols Engr. Co., "Direct Contact Heat Exchanger, 10 kW Power Loop," Lawrence Berkeley Laboratory, LBL-7036, July, 1979.
2. Barber-Nichols Engr. Co., "Design Definition of a 500 kW Direct Contact Geothermal Pilot Plant," Lawrence Berkeley Laboratory, UCID 8009, March, 1978.
3. Barber-Nichols Engr. Co., "Final Design, Installation, and Baseline Test of 500 kW Direct Contact Pilot Plant at East Mesa," Lawrence Berkeley Laboratory LBL-11153, May, 1980.

The components in the recovery system performed functionally to expectation. The recovery compressor maintained the recovery flash tank at the 5 psia design level even with higher than 50 ppm design value of CO₂ in the effluent brine. The actual performance level achieved by the recovery system will be determined in the follow on test series presently underway.


Fig. 1

PROCESS FLOW DIAGRAM
500 KW DCHX PILOT PLANT




STREAM	MATERIAL BALANCE																												
	PROCESS STREAM NUMBER																												
	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27			
PARAMETER	GEOTHERMAL BRINE SUPPLY	GEOTHERMAL BRINE TO BOOST PUMP	GEOTHERMAL BRINE TO DCHX	SOLUBLE VAPOR FROM DCHX	SOLUBLE VAPOR TO TURBINE	SOLUBLE VAPOR TO CONDENSER	CONDENSATE TO HOTWELL	SOLUBLE CONDENSATE TO HOTWELL	SOLUBLE LIQUID TO FEED PUMP	SOLUBLE LIQUID FROM FEED PUMP	SOLUBLE LIQUID TO DCHX	GEOTHERMAL BRINE FROM DCHX	GEOTHERMAL BRINE FROM PFD TURBINE	HEAVY BRINE	BRINE	VENT FROM RECOVERY FLASH TANK	VENT FROM RECOVERY FLASH TANK	CONDENSATE FROM IC ₂ RECOVERY CONDENSER	CONDENSATE TO EVAPORATOR	IC ₂ TO EVAPORATOR	EVAPORATOR	WATER CONDENSATE FROM HOTWELL TO IC ₂ RECOVERY CONDENSER	IC ₂ RECOVERY CONDENSER	IC ₂ RECOVERY VENT					
FLOW RATE (lb/hr x 10 ³)	978	972	972	994	994	994	994	980	980	980	954	958	972	972	0	0	0	0	0	0	2.6	2.6	1.4	16.0	0.06	140	489		
TEMPERATURE (°F)	340	335	335	295	283.4	140.6	140.6	94.0	94.0	95.0	95.0	468	448	448	448	250	76	335	95	250	94	74	76	270	225				
PRESSURE (PSIA)	175	118	485	432	442	72	72	72	72	72	72	485	467	457	170	5.0	20.0	170	5	90	95	485	460	17	90	95	95		
ENTHALPY (BTU/LBM)	51.4	506	506	581	628	627	627	627	627	627	627	111	112	98	112	98	112	98	112	98	112	608	620	420	420	420	420	420	420
DENSITY (LBM/FT ³)	56.0	56.1	56.2	6.46	6.32	0.692	688	340	33.8	33.8	33.8	33.8	61.4	61.3	61.3	61.3	61.3	61.3	61.3	61.3	61.3	7.0	62.1	62.3	62.3	62.3	62.3	62.3	62.3

FIGURE 2
500 KW PILOT PLANT
DIRECT CONTACT HEAT EXCHANGER
HEATING CURVE (HIGH FLOW CASE)
JAN. 18, 1980 4:29 P.M.



XBL 806-10495

FIGURE 3
PROJECTED & ACTUAL
CONDENSER HEAT
TRANSFER PERFORMANCE
DATA WET BULB TEMPERATURE RANGE 48°F-54°F



XBL 806-10495

This report was done with support from the Department of Energy. Any conclusions or opinions expressed in this report represent solely those of the author(s) and not necessarily those of The Regents of the University of California, the Lawrence Berkeley Laboratory or the Department of Energy.

Reference to a company or product name does not imply approval or recommendation of the product by the University of California or the U.S. Department of Energy to the exclusion of others that may be suitable.

TECHNICAL INFORMATION DEPARTMENT
LAWRENCE BERKELEY LABORATORY
UNIVERSITY OF CALIFORNIA
BERKELEY, CALIFORNIA 94720